SAGAR FOREST DIVISION.

Abstract Notification dated 9th January 1940.

The attention of the public is invited to the detailed Notification published on pages 112-113, Part VI of the *Mysore Gazette,* dated 18th January 1940, regarding the auction sale of timber at the several depots as detailed below :—

No.	*Name of the Depot*	*Date of Sale*
1.	Sagar	2nd March 1940.
2.	Shiralkoppa	22nd February 1940.
3.	Shikarpur	28th February 1940.
4.	Anavatti	23rd February 1940.
5.	Shakunvalli	26th February 1940.

N. VENKATARAMAIYA,
District Forest Officer.

BHADRAVATI DIVISION.

Abstract Notification dated 8th January 1940.

The attention of the public is invited to the detailed notification of date regarding the auction sale of timber in the following depots, published on pages 56-57, Part VI of the *Mysore Gazette,* dated 11th January 1940.

Name of Depot	*Quantity*	*Date of sale*
Channagiri	Teak 5,000 C.ft.	5th February 1940.
Ubrani	,, 2,000 ,,	8th February 1940.

Abstract Notification dated 12th January 1940.

The attention of the public is invited to the detailed Notification published on pages 113-114, Part VI of the *Mysore Gazette,* dated 18th January 1940, regarding tenders for supply of rations to elephants of Bhadravati Division during the year 1940-41.

Notification dated 17th January 1940.

It is hereby notified for general information of the public under Section 40 of the Mysore Forest Act, that the following quantities of timber found lying in a pond near Kagekodamagge of Shimoga Taluk, are kept in the custody of the persons noted against each. Persons having any claim for the timber may prefer their claims within one month from the date of this Notification, failing which, the timber will be confiscated to Government under Section 42 of the said Act.

Teak	25=40 C.ft.	Kept in the custody of Patel, Kagekodamagge.
Matti	33=23 C.ft.	
Junglewood timber	45=22 C.ft.	
Matti	8= 4 C.ft.	In the compound of Mr. S. V. Krishnamurty Rao, Pleader, Shimoga.
Junglewood timber	14= 6 C.ft.	

H. S. RANGACHAR,
District Forest Officer.

ENGINEERING DEPARTMENT.

BUILDINGS DIVISION, BANGALORE.

Abstract Notification dated 3rd January 1940.

The attention of the public is hereby invited to the detailed notification calling for tenders for constructing first floor of Chamber of Commerce, Bangalore, published on pages 57-59, Part VI of the *Mysore Gazette,* dated 11th January 1940. The last date of tender is 26th January 1940.

Abstract Notification dated 5th January 1940.

The attention of the public is hereby invited to the detailed notification calling for tenders for constructing additional rooms to the Kannada Boys' Middle School at new Sawar Lines, Bangalore, published on pages 60-61, Part VI of the *Mysore Gazette*, dated 11th January 1940. The last date of tender is 29th January 1940.

M. K. RAJAM IYENGAR,
Executive Engineer.

BANGALORE DIVISION.

Abstract Notification dated 5th January 1940.

The attention of the public is hereby invited to the detailed notification inviting sealed tenders for restoring and improving Araladibbe Minor Tank, Reg. No. 257 of Nelamangala Taluk, published on pages 61-64 of Part VI of the *Mysore Gazette*, dated 11th January 1940.

The last date for the receipt of the tender is 2 P.M. on 27th January 1940. Duplicate challan for having credited the deposit amount of Rs. 170 into the Treasury under "17 (*a*) P. W. Deposits" should accompany each tender.

Abstract Notification dated 5th January 1940.

The attention of the public is hereby invited to the detailed notification inviting sealed tenders for constructing a building for the Town Hall at Devanahalli, published on pages 64-66 of Part VI of the *Mysore Gazette*, dated 11th January 1940.

The last date for the receipt of the tender is 2 P.M. on 27th January 1940. Duplicate challan for having credited the deposit amount of Rs. 410 into the Treasury under "17 (*a*) P. W. Deposits" should accompany each tender.

Abstract Notification dated 12th January 1940.

The attention of the public is hereby invited to the detailed notification inviting sealed tenders for constructing a masonry anicut at 1/13th mile of Madras-Cannanore Road, Kengeri side, published on pages 115-116 of Part VI of the *Mysore Gazette*, dated 18th January 1940.

2. The last date for the receipt of the tenders is 2 P.M. on 3rd February 1940. Duplicate challan for having credited the deposit amount of Rs. 160 into the Treasury under "17 (*a*) P. W. Deposits" should accompany each tender.

N. LAKSHMINARASIMHAIYA,
Executive Engineer.

BUREAU OF SANITARY ENGINEERING, BANGALORE.

Abstract Notice dated 12th January 1940.

The attention of the public is invited to the Notification calling for tenders for the work of constructing 1st stage drains in Bhadravati Old Town, published in pages 117-118 of Part VI of the *Mysore Gazette*, dated 18th January 1940.

The last date of receiving tenders is fixed on 31st January 1940.

Notification dated 18th January 1940.

Notice is hereby given that sealed tenders will be received from licensed plumbers at the Office of the Sanitary Engineer, Bureau of Sanitary Engineering, Bangalore, up to 1 P.M. on 10th February 1940, for the work of providing Sanitary fittings and Drainage arrangements to the Cricket Stadium behind Central College Hostel at Bangalore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of March 1940.

2. The plans, detailed estimate and conditions may be seen at the Sanitary Engineer's Office between the hours of 11 A.M. and 5 P.M. on all office days.

3. Tenders should be submitted on printed forms which may be obtained from the Sanitary Engineer. On a payment of annas four per form per copy. No tender not in prescribed form will be accepted. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 72 in cash (no cheques will be accepted) as earnest money, and be superscribed "Tender for the work of providing Sanitary fittings and Drainage arrangement to the Cricket Stadium behind Central College Hostel at Bangalore," in default of which the tenders will be rejected.

5. The final acceptance of the tender will rest with the Sanitary Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Sanitary Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Charges on account of scaffolding materials, implements for setting out, barricading, clearing site, supply of water, etc., that may be found necessary during execution will not be paid for separately but should be borne by the contractor.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Sanitary Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of disputes about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Sanitary Engineer will be final and legally binding.

Estimate of the approximate quantities for the work of providing Sanitary Fittings and Drainage arrangements to the Cricket Stadium behind Central College Hostel at Bangalore.

No.	Item of works	Unit	Rate	Quantity	Cost
	Soil, Waste and Waste Connection.		Rs. a. p.		Rs.
1	Providing 4″ C.I. soil pipe with specials such as bends, off-set and junction, etc., laying and jointing complete including painting with red lead paint scaffolding and wall, cornice base and floor, basement grooving and redoing with cement and white or colour wash to suit the building colour, etc., complete	R.ft.		186	
2	Do 3″ C.I. waste pipe as above ..	,,		56	
3	Fixing water closet, lavatory and urinal set complete	No.		10	
4	Do accessories	,,		12	
5	Providing and fixing 4″ zinc cowls	,,		2	
6	Providing 6″×3″ C.I. Nahni trap and constructing cistern with cement concrete and providing and fixing 6″ dia. N.P. grating and cement plastering	,,		2	
7	Providing and fixing ¾″ and ½″ lead pipes with wiped solder joints	,,		16	
8	Do 1½″ for waste	,,		10	
9	Do lead trap 1½″ for urinal lavatory with wiped solder joints	,,		6	
10	Providing and fixing ½″ N.P. stopcocks with union	,,		10	
11	Do ¾″ for shower	,,		2	
12	Do bib cocks N.P. ½″	,,		4	
13	Do ¾″ N.P. shower 6″ dia.	,,		2	
14	Cutting floor earthwork excavation and refilling concrete below the trap and alround the pan and trap, etc., complete	,,		2	
15	Cutting floor earthwork excavation and making 6″ deep and filling concrete 3″ and 1½″ cement concrete and cement plastering with red ochre and removing rubbish, etc., complete ..	,,		2	
16	Painting sanitary fittings and connections, etc., complete	,,		10	
17	Waste connection.—From fitting up to outside walls providing and fixing specials and pipes, grooving wall, and floor and wall bore and redoing with cement and 1″ G.I. pipe, submain ¾″ branches and filling cramps, etc., complete ..	,,		16	
18	Do 1½″ for waste connection as per above	R.ft.		18	
19	Do ¾″ overflow	No.		4	

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
20	Providing and fixing milk white glazed tiles over the lavatory including scraping wall and removing rubbish and repairing with cement damages, walls, etc., complete	S.ft.		72	
	Drainage Arrangements.				
1	Providing S.W. pipe 6″ dia. of tested quality, laying and jointing with cement mortar, earthwork excavation in soil gravel wet earth, soft and hard rock, cutting stoney soil and removing boulders and filling, tamping, watering, forming, etc., including barricading lighting removing all earth and boulders and rock, etc., cleaning the site complete	R.ft.		250	
2	Do 4″ as above	R.ft.		90	
3	Providing and fixing S.W. gully trap of 6″ and 4″ with C.I. grating and constructing cistern with burnt brick in cement mortar and cement plastering and fixing gully trap in cement concrete 6″ alround of bed and providing and fixing hinged lid and frame 12″×10″	No.		2	
4	Constructing circular man-holes of 4 ft. dia. inside with ¾ foot thick bed concrete and 3″ projection outside burnt brick in mortar ¾ foot thick wall alround and top portion being conical in section and cement plastering earthwork excavation hard and soft rock cutting stoney soil and removing boulders and carting surplus earth boulders, etc., and providing and fixing man-hole C.I. cover and frame 21″ dia. (2 cwt.) with cement concrete and cement plastering and tarring man-hole cover and frame complete 3 ft. dia.	No.		1	
5	Do 4 to 5 feet depth	,,		1	
6	Do 5 to 6 feet depth	,,		1	
7	Wall bore and redoing	,,		1	

K. S. HUTCHA RAO,
Sanitary Engineer.

KOLAR DIVISION.

Abstract Notification dated 9th January 1940.

The attention of the public is invited to the detailed notification dated 9th January 1940, published on pages 100-103, Part VI of the *Mysore Gazette*, dated 11th January 1940, regarding tenders for restoring Muniganahalli Minor Tank, Reg. No. 666-407, in Chintamani Taluk.

The last date for receiving tenders is 29th January 1940, up to 2 P.M.

Notification dated 16th January 1940.

1. Sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M. on 5th February 1940, for restoring Chinchandlahalli Doddakere Minor Tank, Reg. No. 224 of Bowringpet Taluk.

2. Tenders in the prescribed form obtainable from the Office of the Executive Engineer, Kolar Division, should be addressed to the Executive Engineer, Kolar Division, in a sealed cover and superscribed as "Tender for restoring Chinchandlahalli Doddakere Minor Tank, Reg. No. 224 of Bowringpet Taluk." The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender must be accompanied by a treasury challan for earnest money of Rs. 280 paid to the treasury to the credit of "17(*a*) P. W. Deposits," against the account of the Executive Engineer, Kolar Division. The earnest money of the successful tenderer will be retained as

security for the due fulfilment of the contract. Such a deposit in cash will not carry any interest.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 5th February 1940 at Kolar. The final acceptance of the tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the departmental Schedule Contract Form, for the due fulfilment of the contract, and for the execution of all items of work in accordance with the Bombay Specifications. A reserve of 5 per cent will be with held in the work bills of the contractor and the same repaid after the due fulfilment of the contract.

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. The earnest money of rejected tenders will be returned on submission of the receipt originally granted, along with an application to the Executive Engineer.

8. Copies of contract documents, schedules and drawings may be seen at any time at the Executive Engineer's Office, Kolar Division, on all working days between 11 A.M. and 5 P.M.

9. Specific rates should be given for each item in the schedule accompanying the tender and the rates should be in rupees, annas and pies and expressed in words and figures. Tenders offering a percentage reduction on the estimate amount will be rejected.

10. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates for such items may be entered in a separate schedule with date and reasons for the same. When lumpsum provisions are shown in schedule of quantities the contractor will be paid at either his tendered rate for each item or the prevailing schedule of rates in the Division at the discretion of the Executive Engineer.

11. No alterations which are made by the tenderers in the tender form in the nomenclature of the items of work will be recognised and if corrections are made, the tenders are liable to rejection.

12. There should be no alterations or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to, and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

13. No reference should be made to the Public Works Department schedule of rates.

14. In the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.

15. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates for the same will be calculated by the Executive Engineer on the basis of current rates for materials and labour with a contractor's profit of 5 per cent as may be approved by the Superintending Engineer. This shall be final and legally binding on the tenderer.

16. The quantities given in the schedule are only approximate and the drawings shown to the contractor are only tentative and are liable to alterations, omissions, deductions or additions, at the discretion of the Executive Engineer or his representative and may be due to any reasons whatsoever. The tendered rates will hold good for any quantity, whether higher or lower than those given in the enclosed schedule.

17. The works should be completed and handed over in a tidy condition to the Public Works Department by the end of May 1940, failing which the Executive Engineer may, at his discretion, levy a penalty of Rs. 5 per day which will ordinarily be calculated at 12 per cent per annum on the total outlay as liquidated damages for non-fulfilment of contract, and will be recovered from the contractor's outstandings for the period exceeded by him beyond the time fixed and until the work is completed and handed over.

18. In all matters of disputes of any kind not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief or the Superintending Engineer shall be final and legally binding.

19. No claim for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reasons for such delays. Contractors should bear this in mind when tendering for the work. Extension of time due to delays caused by the departmental officers will, however, be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools and plant and machinery that will be supplied by the Executive Engineer in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer. The tenderer will pay the hire on tools and plant and machinery as per rules from the date of taking over of such machinery, tools and plant from the Stores to the date of return thereto, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractor should arrange for the payment of royalty and tolls.

Note.—(*a*) The contractor should at his own cost—

(1) Provide rods, stakes, ropes and labour required in setting out the works.
(2) Provide all necessary scaffolding, centering, labour and appliances for hoisting.
(3) Provide mortar mills and sheds, to keep materials under cover and also for workmen.
(4) Arrange for protecting work during inclement weather.
(5) Supply requisite temporary lights, water cisterns, water pumps and hoses, sieves, parahs, shoring, strutting and other requisite protective appliances during the progress of the work.
(6) Supply all water required for work and workmen and shall provide temporary latrines and drains.
(7) Clean away all dirt rubbish, superfluous materials and debris as they accumulate.
(8) Provide arrangements for pumping and baling of water from excavations and foundations wherever and whenever necessary with his own pumping apparatus including necessary leading drains, slump pits, etc.
(9) Afford facilities to any other parties employed upon the work by the P. W. D. so that their work may proceed during the progress of the contract, and give such persons the use of ordinary scaffolding and ladders.
(10) The contractor is responsible for all accidents to workmen, etc., on the work and he must take precaution against all risk of accidents and if necessary provide for the same by insurance at the proper time.

Note.—(*b*) It is the business of the contractor to make his own arrangements for quarries and supplies of materials.

N.B.—Copies of tenders in the prescribed form are obtainable from the Office of the Executive Engineer, Kolar Division, Kolar, only on a payment of four annas per form.

Abstract of quantities for restoring Chunchandlahalli Doddakere Minor Tank, Reg. No. 224 of Bowringpet Taluk.

Item	Description of work	Unit	Rate	Quantity	Cost
	Bund at R. L. 56.50.		Rs. a. p.		Rs.
1	Jungle clearing including removal of roots, etc., complete	Grade	2 0 0	24	48
2	Cutting grips and trenches in the bund for the seat of new earthwork and using the same to bund	,,	2 0 0	24	48
3	Removing ant hills and filling with sand	Each	0 8 0	20	10
4	Earthwork to bund with watering and consolidation including lead	C.yd.	0 3 0	5,013	940
5	Removing and resetting old stone revetment with new jelly wedging	,,	0 8 0	175	88
6	New Stone work	,,	1 8 0	1,741	
6*a*	Earthwork excavation foundation for revetment and using the same to bund	,,	0 2 6	206	
7	Turfing with watering and tamping	S.yd.	0 0 9	6,400	
8	Providing and fixing new grade stones including figuring, painting, etc., complete	Each	1 8 0	25	
9	Do do Index stones	,,	0 6 0	25	
10	Do do new B. M. Stones	,,	2 8 0	2	
11	Do do Register No. stone with date	,,	3 0 0	1	
	Constructing a new C. I. pipe sluice of 6" dia. at R. L. 46.00.				
1	Cutting open the bund and dismantling the old barrels and refilling with consolidation	L. S.			
2	Cutting open the bund for the new sluice and refilling the same with available earth with watering and consolidation	C.yd.	0 5 0	97	

6 C

Item No.	Description of work	Unit	Rate	Quantity	Rate to be offered
			Rs. a. p.		Rs.
3	Earthwork excavation foundation and using the earth to bund	C.yd.	0 2 6	5	
4	Concrete in surki mortar	C.ft.	0 4 0	70	
5	Burnt size stone in surki mortar including bond stones	,,	0 4 6	125	
6	Burnt stone slabs 6″ thick dressed and fixed in surki mortar	S.ft.	0 4 6	104	
7	Pointing with cement mortar 1 : 3 proportion ..	Sqr.	3 8 0	1·50	
8	Drilling holes	Each	0 8 0	4	
9	Providing and fixing 6″ dia. C. I. pipes including Railway Freight and carting to site, etc., complete	R.ft.	3 0 0	36	
10	Providing new plug and rod with locking arrangements		L. S.		
	Constructing a masonry waste weir at R. L. 52.00 to a length of 65 ft.				
1	Earthwork excavation foundation	C.yd.	0 2 6	41	
2	Stone jelly concrete in surki mortar	C.ft.	0 4 0	300	
3	Burnt size stone in surki mortar with bond stones	,,	0 4 0	678	
4	Burnt stone slabs 6″ thick dressed and fixed in surki mortar	S.ft.	0 4 6	389	
5	Cement pointing after raking joints	Sqr.	3 8 0	5.79	20
6	Cutting joggle joints and fixing in cement mortar	Each	0 8 0	13	
7	New rough stone apron with jelly wedging ..	C.yd.	1 8 0	41	
8	Boulder filling below apron	,,	0 12 0	19	

Notification dated 19th January 1940.

1. Sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M. on 20th February 1940, for constructing one block of Line Inspector's Quarters at Bethamangala, Bowringpet Taluk.

2. Tenders in the prescribed form obtainable from the Office of the Executive Engineer, Kolar Division, should be addressed to the Executive Engineer, Kolar Division, in a sealed cover and superscribed as "Tender for constructing One block of Line Inspector's Quarters." The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender must be accompanied by a treasury chellan for earnest money of Rs. 195 paid to the treasury to the credit of "17 (*a*) P. W. Deposits" against the account of the Executive Engineer, Kolar Division. The earnest money of the successful tenderer will be retained as security for the due fulfilment of the contract. Such a deposit in cash, will not carry any interest.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 20th February 1940 at Kolar. The final acceptance of the tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the departmental schedule contract form, for the due fulfilment of the contract, and for the execution of all items of work in accordance with the Bombay specifications. A reserve of 5 per cent will be withheld in the work bills of the contract and the same repaid after the due fulfilment of the contract.

6. Failure to comply with the condition 5 above, or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. The earnest money of rejected tenders will be returned on submission of the receipt originally granted, along with an application to the Executive Engineer.

8. Copies of contract documents, schedules and drawings may be seen at any time at the Executive Engineer's Office, Kolar, on all working days between 11 A.M. and 5 P.M.

9. Specific rates should be given for each item in the schedule accompanying the tender and the rates should be in rupees, annas and pies and expressed in words and figures. Tenders offering a percentage reduction on the estimate amount will be rejected.

10. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates for such items may be entered in a separate schedule with date and reasons for the same. When lumpsum provisions are shown in the schedule of quantities, the contractor will be paid at either his tendered rate for each item or the prevailing schedule of rates in the Division att he discretion of the Executive Engineer.

11. No alterations which are made by the tenderers in the tender form in the nomenclature of the items of work will be recognised and if corrections are made the tenders are liable to rejection.

12. There should be no alterations or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to, and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

13. No reference should be made to the Public Works Department schedule of rates.

14. In the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof, or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.

15. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates for the same will be calculated by the Executive Engineer, on the basis of current rates for materials and labour with a contractor's profit of 5 per cent as may be approved by the Superintending Engineer. This shall be final and legally binding on the tenderer.

16. The quantities given in the schedule are only approximate and the drawings shown to the contractor are only tentative and are liable to alterations, omissions, deductions or additions, at the discretion of the Executive Engineer or his representative and may be due to any reasons whatsoever. The tendered rates will hold good for any quantity, whether higher or lower than those given in the enclosed schedule.

17. The works should be completed and handed over in a tidy condition to the Public Works Department by the end of September 1940, failing which the Executive Engineer may, at his discretion, levy a penalty of Rs. 5 per day which will ordinarily be calculated at 12 per cent per annum on the total outlay as liquidated damages for non-fulfilment of contract, and will be recovered from the contractor's outstandings for the period exceeded by him beyond the time fixed and until the work is completed and handed over.

18. In all matters of disputes of any kind not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief or the Superintending Engineer shall be final and legally binding.

19. No claim for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reasons for such delays. Contractors should bear this in mind when tendering for the work. Extension of time due to delays caused by the departmental officers will, however, be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools and plant and machinery that will be supplied by the Executive Engineer in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer. The tenderer will pay the hire on tools and plant and machinery as per rules from the date of taking over of such machinery, tools and plant from the Stores to the date of return thereto, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractor should arrange for the payment of royalty and tolls.

Note.—(*a*) The contractor should at his own cost—

(1) Provide rods, stakes, ropes and labour required in setting out the works.
(2) Provide all necessary scaffolding, centering, labour and appliances for hoisting.
(3) Provide mortar mills and sheds, to keep materials under cover and also for workmen.
(4) Arrange for protecting work during inclement weather.
(5) Supply requisite temporary lights, water cisterns, water pumps and hoses, sieves, parahs, shoring, strutting and other requisite protective appliances during the progress of the work.
(6) Supply all water required for work and workmen and shall provide temporary latrines and drains.
(7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.
(8) Provide arrangements for pumping and baling of water from excavations and foundations wherever and whenever necessary with his own pumping apparatus including necessary leading drains, slump pits, etc.
(9) Afford facilities to any other parties employed upon the work by the P. W. D., so that their work may proceed during the progress of the contract, and give such persons the use of ordinary scaffolding and ladders.
(10) The contractor is responsible for all accidents to workmen, etc., on the work and he must take precaution against all risk of accidents and if necessary provide for the same by Insurance at the proper time.

Note.—(*b*) It is the business of the contractor to make his own arrangements for quarries and supplies of materials.

N. B.—Copies of tenders in the prescribed form are obtainable from the office of the Executive Engineer, Kolar Division, Kolar, only on a payment of Re. 0-4-0 per form.

Abstract estimate for the probable cost of constructing one block of Line Inspector's Quarters at Bethamangala.

No.	Items of work	Unit	Rate	Quantity	Rates to be tendered
			Rs. a. p.		
1	Earthwork excavation in ordinary soil for foundation and filling in basement including extra earth required with lead complete ..	C.yds.	0 3 0	59	
2	Burnt stone jelly concrete in chunam mortar for foundation	C.ft.	0 3 6	437	
3	Burnt size stone in clay for foundation and basement with necessary bond stones	C.ft.	0 3 0	1,368	
4	Burnt brick in clay superstructure	C.ft.	0 3 3	1,950	
5	Burnt brick in mortar superstructure	C.ft.	0 4 0	547	
6	Burnt stone slabs 6″ thick dressed and fixed in chunam mortar	S.ft.	0 4 6	169	
7	Burnt stone slabs 4″ thick roughly dressed and fixed over beams in verandah	S.ft.	0 4 0	28	
8	Pointing with cement mortar 1 : 3 proportion alround basement after raking joints deep ..	Sqr.	3 12 0	2.40	
9	Plastering with chunam mortar over brick in mud walls	Sqr.	3 0 0	48.04	
10	White and colour washing two coats	,,	0 5 0	50.44	
11	Plain cornice 9″ deep with burnt brick in mortar including plastering, etc. complete ..	R.ft.	0 7 0	52	
12	Burnt brick in Chunam mortar parapet wall of 9″ thick and 2 ft. high with plastering, etc., complete as per design	R.ft.	1 0 0	50	
13	Flooring with 1½″ thick cement concrete 1 : 2 : 4 proportion on a bed of 3″ thick chunam mortar and burnt stone jelly concrete with cement plastering ½″ thick 1 : 3 proportion and coloured with red ochre including cutting lines to the required patern, etc., complete ..	Sqr.	18 0 0	8.40	
14	Roofing with First Class Mangalore tiles on T.W. reepers of 2″×1″ with wood oiling to reepers, etc., complete	Sqr.	26 0 0	12.03	
15	Ridge tiles set in cement mortar	R.ft.	0 7 6	73	
16	R.C.C. terrace 6 inches thick cement concrete 1 : 2 : 4, with reinforcement bars as per design for carrying a superload of 80 lbs. with surki mortar concrete and two course of flat tiles surface and ceiling plastered with proper slope where necessary including curving, etc., complete	Sqr.	65 0 0	2.89	
17	Teakwood work first class wrought and put up including wood oiling, two coats	C.ft.	5 0 0	64	
18	Plain teakwood eave board ¾″×9″ wide fixed with painting	R.ft.	0 7 0	130	
19	Teakwood First Class doors 3½″×4½″ with battened shutter 1″ thick including fixtures, etc., complete	S.ft.	1 4 0	163	
20	Teakwood First Class Windows, frame 3½″×4½″ and shutter of 1″ thick, half battened and half glazed with iron bars, including necessary fixtures	S.ft.	1 14 0	110	
21	Teakwood First Class cup-boards with battened shutters of 1″ thick, and providing T.W. planks inside including painting, two coats complete with necessary fixtures	S.ft.	1 8 0	48	
22	Providing and fixing, T.T.R. Steel Girders, including Railway freight, carrying, lifting, hoisting with painting, two coats, etc., complete	Cwt.	14 0 0	4.50	
23	Expanded metal 3″×1½″ with ⅛′ stranded with T.W. framed work fixed complete ..	S.ft.	0 10 0	111	
24	Painting, two coats of approved green paint prepared by the Mysore Lac Factory ..	Sqr.	3 8 0	11.17	
25	Providing and fixing ventilating tiles	No.	2 8 0	6	

No.	Items of work	Unit	Rate	Quantity	Rates to be tendered
			Rs. a. p.		Rs.
26	Constructing sinks with burnt brick in mortar and cement plastering ½" thick	Each	5 0 0	2	
27	Providing stone mortar and pestle	,,	5 0 0	1	
28	Chunam mortar band over roof with plastering complete	R.ft.	0 6 0	26	
29	Providing and fixing rain water down pipes 3" dia. of Galvanized Iron sheet complete	R.ft.	0 8 0	50	
30	Constructing chimneys in kitchin and bath rooms as per design	L.S.		2	
31	Levelling ground and clearing site, etc.	,,			
32	Constructing ½ unit of latrine complete as per plan	,,			

C. R. IYENGAR,
Executive Engineer.

TUMKUR DIVISION.

Abstract Notification dated 3rd January 1940.

The attention of the public is drawn to the Notification calling for tenders for collection of burnt stone jelly in miles 71 to 98 (both inclusive) of Bangalore-Honnavar road, published in pages 67-68, Part VI of the *Mysore Gazette*, dated 11th January 1940.

2. The tenders will be received by the Executive Engineer up to 2 P.M. on 26th January 1940.

3. The earnest money required for the work is Rs. 50 for each section of mile, which should be credited to the treasury to "17 (*a*) P. W. Deposits" and the relative chellan enclosed.

Abstract Notification dated 13th January 1940.

The attention of the public is drawn to the Notification calling for tenders for restoring the breached Kagglodu Major Tank, Reg. No. 146, Sira Taluk, published in pages 119-120, Part VI of the *Mysore Gazette*, dated 18th January 1940.

2. The tenders will be received by the Executive Engineer up to 2 P.M. on 2nd February 1940.

3. The earnest money required for the work is Rs. 315 which should be credited to the treasury to "17 (*a*) P. W. Deposits" and the relative chellan enclosed.

Abstract Notification dated 13th January 1940.

The attention of the public is drawn to the Notification calling for tenders for raising the weirs of Haldodderi Major Tank, Reg. No. 211 of Sira Taluk, published in pages 120-121, Part VI of the *Mysore Gazette*, dated 18th January 1940.

2. The tenders will be received by the Executive Engineer up to 2 P.M. on 9th February 1940.

3. The earnest money required for the work is Rs. 450 which should be credited to the treasury to "17 (*a*) P. W. Deposits" and the relative chellan enclosed.

P. RAJAGOPALAN,
Executive Engineer.

OFFICE OF THE ASSISTANT ENGINEER, HEADQUARTER RANGE, MYSORE.

Notification dated 19th January 1940.

1. Sealed tenders will be received at the Office of the Assistant Engineer, Headquarter Range, Mysore, up to 2 P.M. on 5th February 1940, for constructing a building for Medical Officers' quarters, P. K. Sanatorium, Mysore.

2. Tenders in the prescribed form obtainable from the Office of the Assistant Engineer, Headquarter Range, Mysore, on payment of four annas for each form, should be addressed to the

Assistant Engineer, Headquarter Range, and should be superscribed as "Tender for constructing a building for Medical Officers' quarters in P. K. Sanatorium, Mysore." The name of the tenderer should also be superscribed on the sealed cover.

3. Each tender must be accompanied by a deposit of Rs. 450 only in cash (at cash payment value at the time of deposits and not face value), as earnest money. The earnest money of the successful tenderer will be retained as cash security for due fulfilment of the contract. (Cash amount will not carry any interest.) The amount of earnest money should be paid direct to the Treasury and the duplicate Treasury chellan submitted separately along with the tender.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 5th February 1940 at 4 P.M. The final acceptance of the tender will rest with the Superintending Engineer, who does not bind itself to accept the lowest or any tender, or to assign any reasons whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Assistant Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute the agreement in the departmental schedule contract form for the due fulfilment of the contract.

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. Copies of contract documents, estimates and drawings may be seen at any time at the Office of the Assistant Engineer, Headquarter Range, Mysore, on all working days, between 11 A.M. and 5 P.M.

8. Specific rate should be given for each item in the schedule and the rates should be in rupees, annas and in multiples of three pies and expressed in words and figures.

9. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer will not be taken notice of. The rates tendered should include all such lumpsum items.

10. No alterations which are made by the tenderers in the contract documents in the nomenclature of the sanctioned sub-heads will be recognised and if corrections are made, the tenders will be liable to rejection.

11. There should be no corrections or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

12. No reference should be made to the Public Works Department current schedule of rates.

13. On the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.

14. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates to be proposed by the Assistant Engineer, Headquarter Range, Mysore, and approved by the Superintending Engineer shall be final and legally binding on the tenderer.

15. The quantities as estimated are only approximate and are liable to alterations, omissions, deductions or additions, at the discretion of the Assistant Engineer or his representative. The tendered rates will hold good for any quantity whether higher or lower than those estimated for.

16. The work should be completed as per departmental specifications for different items and handed over to the Public Works Department within three months from the date of issue of order for commencement of the work, failing which the Assistant Engineer may, at his discretion, levy a penalty up to Rs. 10 per day, of delay, which will be recovered from the contractor's outstandings for the period exceeded by him till the work is completed and handed over.

17. In all matters of dispute of any kind, not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief Engineer shall be final and legally binding.

18. The earnest money of rejected tenders will be returned on surrender of the receipts originally granted, along with an application to the Assistant Engineer, Headquarter Range, Mysore.

19. No claims for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reason for such delays. Contractors should bear this in mind when tendering for work. Extension of time due to delays caused by the departmental officers will, however, be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools, plant and machinery, that will be supplied by the Assistant Engineer in the interest of the work, shall be accepted by the tenderer at the rates fixed by the Assistant Engineer, and the tenderer will pay the hire, etc., on machinery at the prescribed per cent per annum of the booked value of the tools and plant supplied from the date of taking over of tools and plant from the Stores to the date of return to the Stores, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractors should arrange for the payment of royalty and tolls.

NOTE.—(*A*) The contractor should at his own cost—

(1) Provide rods, stakes, ropes and labours required in setting out the works.
(2) Provide all necessary scaffolding, centering labour and appliances for hoisting.
(3) Provide mortar mills and sheds to keep materials under cover and also for workmen.
(4) Arrange for protecting work during inclement weather.
(5) Supply requisite temporary lights, water cisterns, water-shoots, coverings to masonry, tile pieces to steps, sieves, parahs or measures, shoring and other requisite protection during the progress of the work.
(6) Supply all water required for work and workmen and shall provide latrines, drainages, etc.
(7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.
(8) Provide arrangements for pumping and baling from excavations and foundations, wherever and whenever necessary, with their own pumping apparatus including necessary leading drains, slump pits, etc.
(9) Wash floors at completion and leave the whole of the work and premises in a clean and orderly condition, etc.
(10) Afford facilities to any other parties employed upon the work, so that their work may proceed during the progress of the contract and give such persons the use of ordinary scaffolding and ladders.

NOTE.—(*B*) It is the business of the contractors to make their own arrangements for the quarries and supplies of materials.

23. The rates for woodwork for all works quoted should be based on the rates of the departmental supply as noted below. Only Mysore teak selected from the Mysore Government Depots must be used.

24. Work to the extent of Rs. 3,000 will have to be carried out each month.

Prevailing Government rates at Mysore Forest Depot for Mysore Teak is as follows :—

	Rs.	a.	p.	
(1) Selected 1st class logs	2	8	0	per c.ft.
(2) Cut scantling of sizes 3″×4″	3	4	0	,,
(2*a*) Do 3″×5″ to 4″×7″	3	12	0	,,
(3) Planks 1″ to 1¾″ to required sizes	4	8	0	,,

25. Only Chamundi Brand cement should be used for all works requiring this nature.

26. Such of the tenders which do not clearly quote with detailed specification for all the items without exception, will not be considered.

Abstract Estimate for constructing Medical Officers' Quarters in P. K. Sanatorium, Mysore.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
1	Clearing the site and levelling ground	L. S.			
2	Earthwork excavation in gravelly soil and filling in basement	C.yd.		132	
3	Burnt stone jelly concrete in lime mortar	C.ft.		1,226	
4	Burnt size stone in chunam mortar with bond slabs foundation and basement	,,		3,303	
5	Burnt brick in clay including necessary scaffolding, etc., complete	,,		5,108	
6	Burnt brick in mortar	,,		485	
7	Cement concrete (1 : 2 : 4) for top of walls, cills of windows, wall shelves, etc.	,,		461	
8	Flooring with 1½″ cement concrete over 3″ chunam concrete and ½″ red cement plastering cut to tile pattern, etc., complete	Sqr.		423·98	
9	Flooring with 3″ to 4″ thick burnt stone slabs on 3″ concrete bed with 2 line dressing and cement pointing	,,		5·38	
10	Burnt stone slabs 6″ thick with one line dressing, fixed in mortar	S.ft.		721	
11	Two line dressing to burnt stone slabs on all exposed faces	,,		158	
12	Teakwood doors with panelled shutters 1½″ thick frame 4″×5″ with brass fittings complete	,,		373	

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
13	Teakwood battened doors with 1½″ shutters and 3″×4″ frame with iron fittings complete	S.ft.		239	
14	Teakwood panelled windows with 3½″×4½″ frames and with glazed shutters and brass fittings, etc., complete	,,		44	
15	Teakwood panelled shutters and iron bars, etc., complete	,,		203	
16	Teakwood battened windows with iron-fittings and iron bars, etc., complete	,,		68	
17	Providing and fixing weld-mesh with teak wood frame work, etc., complete	,,		243	
18	Teakwood wall shelves with panelled shutters 3″×4″ frame with intermediate 1″ thick planks and brass fittings complete	,,		121·50	
19	Cutting grooves in the cill slab for door frame seating vertically	No.			
20	Roofing with R.B.C. terrace above 10′ span as per specification including 3″ kappi and flat tiles with coveing including plastering top and bottom complete	Sqr.		24·00	
21	Rolled steel joists and girders with one coat of anti-corrosive or other paint including hoisting, boxing, etc., complete	Cwt.		34·00	
22	Teakwood work wrought and put up complete	C.ft.		46·20	
23	Roofing with Mangalore tiles (Yelahanka) on teak reepers 2″×1″ complete	Sqr.		12·44	
24	Mangalore ridge tiles set in mortar	R.ft.		68	
25	Parapet wall 15″ high 9″ thick with receding offsets complete in brick in mortar	R.ft.		304	
26	Band cornice work complete	,,		304	
27	Chunnam plastering	Sqr.		117·87	
28	White and colour washing two coats complete	,,		117·87	
29	Providing and fixing 2″ galvanized pipes for outlets above floor level	No.			
30	Providing and fixing cement asbestos rectangular rain water pipes with bend, etc., complete	R.ft.		144	
31	Providing and fixing teakwood plank 1″ thick with iron brackets	S.ft.		16	
32	Polishing doors with approved polish	Sqr.		8·50	
33	Laboratory green paint 2 coats	,,		14·20	
34	Forming the valley including 1″ thick teakwood plank 2½′ plain zinc sheet with mortar band, etc., complete	S.ft.		51	
35	Teakwood ventilators with glazed shutters, etc., complete	,,		54	
36	R.C.C. fret work over windows complete including frame, etc.	S.ft.		10	
37	R.C.C. chajja 4″ thick	,,		28	
38	Pillars with wire cut brick in cement mortar with base and capital including plastering, etc., complete with bond slabs	R.ft.		32	
39	Teakwood pillars with base and capital 6′×6″×6″ complete	No.		6	
40	Teakwood eave board as per design	R.ft.		134	
41	Chunnam borders 4½″×6″ complete	,,		65	
42	Teakwood frame with weld mesh as per approved design	S.ft.		174	
43	Constructing lead off drain in cement concrete, etc., complete	R.ft.		75	
44	Constructing oven cisterns and chimney in bath and kitchen	L. S.			
45	Cement pointing	Sqr.		4·54	
46	Providing and fixing mortar and pestle	No.		2	
47	Constructing exmetal walls with burnt brick in cement mortar with Xmet at every 3rd course including chunnam plastering, etc., complete	S.ft.		679	

M. N. LAKSHMAN RAO,
Assistant Engineer

KADUR DIVISION.

Notification dated 19th January 1940.

1. Sealed tenders will be received at the Office of the Executive Engineer, Kadur Division, Chikmagalur. up to 3 P.M. on 12th February 1940, for the work of providing additional accommodation to the Kannada Middle School at Kadur during.

2. Tenders in the prescribed form obtainable from the Office of the Executive Engineer, Kadur Division, should be addressed to the Executive Engineer, Kadur Division, Chikmagalur in a sealed cover and superscribed as "Tender for the work of providing additional accommodation to the Kannada Middle School at Kadur." The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender must be accompanied by a Treasury chellan for Rs. 200 (Rupees two hundred only) for having credited this earnest money to 17 (*a*) P. W. Deposits in any approved Government Treasury. The earnest money of the successful tenderer will be retained as security deposit for due fulfilment of the contract. Such a deposit will not carry any interest. Tenders unaccompanied by earnest money will not be accepted.

4. The tenders will be opened in the presence of such tenderers as wish to be prese n on 12th February 1940 at Chikmagalur. The final acceptance of the tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the departmental Schedule Contract Form, for the due fulfilment of the contract.

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force, will entail forfeiture of the earnest money.

7. The earnest money of rejected tenders will be returned on submission of the receipt originally granted, along with an application to the Executive Engineer.

8. Copies of contract documents, schedules and drawings may be seen at any time at the Executive Engineer's Office, Chikmagalur, on all working days between 11 A.M. and 5 P.M.

9. Specific rates should be given for each item in the schedule accompanying the tender and the rates should be in rupees, annas and pies and expressed in words and figures.

10. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates for such items may be entered in a separate schedule with date and reasons for the same.

11. No alterations which are made by the tenderers in the tender form in the nomenclature of the items of work will be recognised and if corrections are made, the tenders are liable to rejection.

12. There should be no alterations or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to, and the number of corrections if any, in each page noted at the foot of the same by the tenderer.

13. No reference should be made to the Public Works Department schedule of rates.

14. In the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.

15. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates for the same will be calculated by the Executive Engineer on the basis of current rates for materials and labour with a contractor's profit of 5 per cent as may be approved by the Superintending Engineer. This shall be final and legally binding on the tenderer.

16. The quantities given in the schedule are only approximate and the drawings shown to the contractor are only tentative and are liable to alterations, omissions, deductions or additions, at the discretion of the Executive Engineer or his representative. The tendered rates will hold good for any quantity, whether higher or lower than those given in the enclosed schedule.

17. The works should be completed and handed over in a tidy condition to the Public Works Department by the end of June 1940, failing which the Executive Engineer may, at his discretion, levy a penalty of Rs. 100 per fortnight which will be recovered from the contractor's outstandings for the period exceeded by him beyond the time fixed and until the work is completed and handed over.

18. In all matters of disputes of any kind not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Superintending Engineer shall be final and legally binding.

19. No claim for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reasons for such delays. Contractors should bear this in mind when tendering for the work. Extension of time due to delays caused by the departmental officers will, however, be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools and plant and machinery that will be supplied by the Executive Engineer in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer. The tenderer will pay the hire on tools and plant and machinery as per rules from the date of taking over of such machinery, tools and plant from the Stores to the date of return thereto, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. Chamundi brand cement must be used for the work.

23. The contractor should arrange for the payment of royalty and tolls.

Note.—(*a*) The contractor should at his own cost—

(1) Provide rods, stakes, ropes and labour required in setting out the works.
(2) Provide all necessary scaffolding, centering, labour and appliances for hoisting.
(3) Provide mortar mills and sheds, to keep materials under cover and also for workmen.
(4) Arrange for protecting work during inclement weather.
(5) Supply requisite temporary lights, water cisterns, water pumps and hoses, sieves, parahs, shoring, strutting and other requisite protective appliances during the progress of the work.
(6) Supply all water required for work and workmen and shall provide temporary latrines and drains.
(7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.
(8) Provide arrangements for pumping and baling of water from excavations and foundations wherever and whenever necessary with his own pumping apparatus including necessary leading drains, slump pits, etc.
(9) Afford facilities to any other parties employed upon the work by the P. W. D., so that their work may proceed during the progress of the contract, and give such persons the use of ordinary scaffolding and ladders.
(10) The contractor is responsible for all accidents to workmen, etc., on the work and he must take precaution against all risk of accidents and if necessary provide for the same by insurance at the proper time.

Note.—(*b*) It is the business of the contractor to make his own arrangements for quarries and supplies of materials.

Abstract estimate for constructing Additional Accommodation in Kannada Middle School at Kadur.

Item No.	Description of work	Unit	Contents	Total
				Rs.
1	Removing the existing Mangalore tiled roof and stacking released materials such as tiles, reepers, etc.	Sqrs.	24·36	
2	Dismantling burnt brick in mortar in front verandah ..	C.ft.	694	
3	Dismantling basement of side portion removing flooring and clearing debris	L.S.	..	
4	Earthwork excavation for foundation and filling in basement including watering and tamping	C.yd.	46	
5	Burnt stone jelly concrete in lime mortar for foundations 1 : 3.	C.ft.	248	
6	Size stone in mud for foundation and basement including bond stones at every 6′ in each course	C.ft.	1,029	
7	Burnt stone slabs 6″ thick roughly dressed fixed in mortar including two lines dressed the exposed faces	S.ft.	494	
8	Burnt brick in lime mortar for superstructure	C.ft.	2,983	
9	Burnt brick in lime mortar pillars $1\frac{1}{2}' \times 1\frac{1}{2}' \times 8'$ high with through bond slabs at verticle intervals of 2 ft. with plastering, white washing, etc., complete	No.	4	
10	Providing and fixing teakwood doors with panelled shutters including hinges, bolts, nuts and locking arrangements, etc., complete as per design to be approved	S.ft.	62	
11	Providing and fixing teakwood windows with iron bars half panelled and half glazed shutters cut into four halves with iron fittings, etc., complete	S.ft.	233	
12	(*a*) Teakwood wrought and put up including, two coats of wood oiling	C.ft.	107·11	
	(*b*) Teakwood wrought and put up with available materials including necessary repairs and two coats of wood oiling ..	C.ft.	96·8	
13	(*a*) Roofing with 1st Class Mangalore tiles on teakwood reepers including wood oiling to reepers	Sqr.	11·67	

Item No.	Description of work	Unit	Contents	Total
				Rs.
	(*b*) Roofing with available materials with necessary wood oiling, etc.	Sqr.	19.48	
14	(*a*) Ridge tiles set in mortar and cement pointing	R.ft.	101	
	(*b*) Ridge tiles set in mortar with available ridge tiles ..	R.ft.	100	
15	Constructing valley with teakwood planks 6″×$\frac{3}{4}$″ and zinc sheet fixed in cement mortar including plastering, etc., complete	R.ft.	60	
16	(*a*) Providing and fixing teakwood eave board $\frac{3}{4}$″ thick and 9″ deep including painting, etc., complete as per existing design	R.ft.	123	
	(*b*) Fixing available eave board including painting	R.ft.	181	
17	Lime mortar plastering	Sqr.	52.02	
18	White washing two coats as per plastering	Sqr.	52.02	
19	Flooring with 1$\frac{1}{2}$″ cement concrete 1 : 2, : 4 on a bed of 3″ lime concrete 1 : 3 with cement plastering 1 : 2 $\frac{1}{2}$″ thick top finished smooth as per specification, etc., complete ..	Sqr.	7.68	
20	Painting to doors and windows two coats with Lac Factory green paint	Sqr.	6.05	
21	Cement pointing to basement 1 : 3 after raking open joints $\frac{1}{2}$″ to 1″ deep	Sqr.	3.22	
22	Constructing burnt brick in cement mortar circular pillars with base and capital as per design with bond slabs 2′ verticle intervals including plastering white and colour washing, etc. complete	No.	6	
23	Providing R.C.C. beams 1 : 2 : 4 over pillars with necessary reinforcements cast in site including plastering to exposed faces with 1 : 3 cement mortar including centering, etc. ..	C.ft.	36	
24	Constructing mortar band cornice	R.ft.	46	
25	Constructing burnt brick in cement mortar parapet wall 4$\frac{1}{2}$″ thick, 1$\frac{1}{2}$′ height including plastering, white washing, etc., complete	R.ft.	43	
26	Removing the existing door and stacking	No.	2	
27	Providing and fixing teakwood finials as per approved design ..	,,	4	
28	Providing and fixing teakwood pendants as per approved design	,,	12	

M. A. RAMANUJAM,
Executive Engineer.

CHITALDRUG DIVISION.

Notification dated 15th January 1940.

It is notified for the information of the travelling public that the undermentioned Travellers' Bungalows will not be available for travellers, on dates noted against them, as they are reserved for Government purposes.

Davangere T. B. .. From 26th January 1940 to 31st January 1940 (both days inclusive).

Chitaldrug T. B. .. From 28th January 1940 to 3rd February 1940 (both days inclusive).

**Abstract Notification dated 11th January 1940.*

The attention of the public is invited to the tender Notification for providing "Additional Accommodation in the District Lock-up at Chitaldrug," published in the *Mysore Gazette*, dated 18th January 1940, Part VI, pages 122-126.

The last date of tender is 5th February 1940.

B. TIRUMALACHAR,
Executive Engineer.